

MEMORANDUM

Houston, Texas,
January 26, 1928.

HOUSTON NEGRO HOSPITAL
Water System

W. T. Sinclair, Secretary,
Building.

I am submitting revised estimate and print on the
above, in line with Mr. Cullinan's request January 23rd:

1800 - ft. 2" second hand pipe	@ \$.09	\$162.00
Hauling and asphaltting pipe		36.00
¹ Tee 2 x 2		
26 - Tees 2 x 2 x 3/4	@ .20	5.20
6 - Ells 2"	@ .20	1.20
30 - Ells 3/4	@ .10	3.00
2 - Unions 2"	@ 1.00	2.00
2 - Valves 2"	@ 3.25	6.50
26 - Hose bibbs	@ .90	23.40
14 - Pipe threads 2"	@ .20	2.80
30 - pcs. 3/4" pipe 2 ft.	@ .25	7.50
Excavating and backfilling		84.00
Fitting pipe		<u>25.00</u>
		\$ 358.60

The 2" pipe will be purchased from the Petroleum
Supply Company, and asphalted.

The question as to tapping the main and placing the
meters is being taken up with the city council by Mr. House.

J. E. WOODING

JEW-CZ

JSC(Ho-NY-HS)

Asphalt ? ^{24 feet}
Labor ?